

INDUSTRY:

Mining

LOCATION:

Saskatchewan

SCOPE OF WORK:

- Refurbish 110' diameter thickener tank
- Construct a site-approved access ramp into thickener tank
- Coordinate cleanout of thickener tank
- Coordinate 3rd party NDE inspection of tank
- Coordinate grit-blast of required repair areas
- Complete 70% floorplate replacement
- Coordinate 3rd part NDE inspection of new floorplate welds
- Complete vac-box test of new floorplate
- Reinstall door-sheet
- Coordinate grit-blast and internal lining of new floorplate
- Complete hydrotesting

QUALITY:

- API 653, 5th Edition Addendum 1
- 3rd party visual inspection
- 3rd party MPI inspection
- Full vacuum box, including corner box
- Floor was butt-welded with backing bars

SCHEDULE:

Completed on schedule during plant turnaround

CONTRACT TYPE:

Lump Sum

SPECIALTY ITEMS:

- Construction of elevated tank access ramp
- Butt-welded floor with backing bars

SAFETY:

TRIF 0.0

REFERENCE CONTACT:

Available Upon Request

Project Number: MB564

